



PREPARED FOR:
ARPIT DALAL
Nagpur, , Maharashtra

TECHNICAL SPECIFICATIONS

High-performance components designed for maximum efficiency and longevity.

1. SYSTEM OVERVIEW

- Capacity: 2.67 kWp
- Type: Grid-Tied (On-Grid)

kWp represents the peak power output under standard test conditions.

3. INVERTER DETAILS

- Capacity: 2.67 kW
- Pure Sine Wave
- App-Based Monitoring

Converts DC to AC with 98% efficiency and tracks performance via your phone.

5. MOUNTING STRUCTURE

- Galvanized Iron (HDGI)
- Wind Speed: 150 km/h
- Corrosion Resistant

Engineered to withstand heavy winds and extreme weather for 25+ years.

2. SOLAR PANELS

- Quantity: 7 Nos.
- Type: Mono-PERC
- Durability: IP68 Rated

High-efficiency panels that capture more sunlight even in low-light conditions.

4. ENERGY GENERATION

- Estimated: 3,650 kWh/yr
- Monthly: ~304 Units

This system can power approx. 4 ceiling fans, 1 fridge, and all LED lights daily.

6. ELECTRICAL & SAFETY

- DC/AC Distribution Boxes
- Lightning Arrester
- Dual Earthing System

Complete protection against voltage surges and lightning strikes.

INVESTMENT SUMMARY & COST BREAKDOWN	
Solar Panels (7 Nos.)	Rs. 1,33,830
Solar Inverter (2.67 kW)	Rs. 36,499
High-Strength Mounting Structure	Rs. 24,333
Electricals, Wiring & Conduit	Rs. 17,033
Installation & Commissioning	Rs. 14,600
Protection System (ACDB/DCDB, Earthing)	Rs. 9,733
Transport & Miscellaneous	Rs. 7,300
Subtotal (Value of Goods & Services)	Rs. 2,43,328
GST (Goods & Services Tax @ 13.8%)	Rs. 33,579
TOTAL PROJECT COST (Turnkey)	Rs. 2,76,907
EXPECTED SAVINGS & ROI	
Annual Savings: Rs. 29,200	
Payback Period: 9.5 Years	
Net 25-Year Life Cycle Gain: Rs. 7,30,000	